

NOTICE IS HEREBY GIVEN that the Board of County Commissioners of Hill County, Montana, will receive sealed written bids at their office in the Hill County Courthouse, 315 4th St., Havre, MT, 59501, until 4P.M. local time, on the 11th of December, 2025, subject to Section 7-5-2301, M.C.A., for the Flood Repairs to be done within Beaver Creek Park. After this hour, no bids will be accepted.

Each bid must be signed and submitted on a Hill County Bidder Response Form, and submitted in a sealed envelope addressed to the Board of Commissioners, 315 4th St., Havre, MT, 59501. The envelope shall be plainly marked on the outside as a Bid for BCPark Flood Repairs, and the envelope must bear on the outside this bidder's name and address. If the bid is forwarded by mail, the sealed envelope containing the bid must be enclosed in a separate envelope addressed to the Board of Commissioners. Bids by telephone, fax or telecommunications will not be accepted.

Work location will be within Beaver Creek Park roughly 20-25 miles from Havre.

Further information on location, bidding questions, or to obtain a Bidder Response Form, contact the Beaver Creek Park Office at (406)-395-4565.

All bids shall remain effective for a term not to exceed sixty (60) days from the day of opening. Hill County reserves the right to reject any or all bids, to waive any defect of irregularities, or to accept any bid they deem to be in the best interest of Hill County.

The Hill County Parks Department (Beaver Creek Park) is requesting bids for flood damage repair from the 2024 disaster declaration. Repairs include road repairs (shaping of roads and placing of assorted gravel materials), installation of 12 conveyor belt water bars at two locations, replacing a small 18" culvert, and removal of a damaged pedestrian bridge.

All projects are 20-25 miles from Havre. Material quantities include 1,239 cubic yards of 1 ½" surface gravel, 746 cubic yards of aggregate base course (ABC), 293 cubic yards of crusher fines, 10 water bars 16' x 5" x 12" H, 2 water bars 20' L x 5" x 12" H, and 1 culvert 18" x 20'.

More details and approximate locations are listed in the information below in order from North to South.

****Project KC 4:** Replace 23cy of 1 ½" surface gravel approximately 70' L x 15' W x 3" H. **Location Approximately 19 miles South of Havre.**

****Dumpster Road:** Install 43cy of 1 ½ " surface gravel approximately 310' x 15' x 3". Replace surface gravel lost. Install 23cy of Aggregate Base Course approximately 310' x 1'Wx 2'H. Replace Base lost to fill gully. Clean ditch out to allow water to divert to dispose of materials nearby at Park specified location approximately 310' x 1' W. Clean out roadside ditch. Install two water bars made of 2 x 6 treated lumber and recycled conveyor belt material 20' L x 5"x 12" H.

Location Approximately 19 miles South of Havre.

****Kiwanis, Office Roads, Shop & Chapel:** Replace 437cy of 1 ½" surface gravel lost approximately 2,529' L x 14' W x 4". Replace 170cy of 1 ½ " surface gravel approx. 573' L x 24' W x 4" D

Location Approximately 19 miles South of Havre.

****Shambo 6, 10, 11:** Replace 13cy of 1 ½ " surface gravel approximately 60' L x 14' W x 3". **Location Approximately 20.8 miles South of Havre.**

****Doney RP#2:** Replace 20cy of 1 ½ " surface gravel approximately 117' L x 14' W x 4". **Location Approximately 21 miles South of Havre.**

****Mo10:** Remove bridge from creek and take it to landfill.

Location Approximately 21.5 miles South of Havre.

****MO 16:** Replace 15cy of 1 ½ " surface gravel approximately 115' long x 15' wide x 3" deep **Location Approximately 21.5 miles South of Havre.**

****Pagers North Road:** Install 330cy of 1 ½" surface gravel approximately 2,224' L x 16' W x 3" D.

Location Approximately 22.5-23 miles South of Havre.

****CB 8:** Install 5cy of 1 ½ " surface gravel approximately 40' L x 14' W x 3". Replace surface gravel lost on the road.

Location Approximately 23 miles South of Havre.

****CB 9:** Install 11cy of 1 ½ " surface gravel approximately 110' L x 10' W x 3". Replace surface gravel lost at entry to CB9/ Gomke campground.

Location Approximately 23 miles South of Havre.

****CB 10:** Install 185cy of ABC material approximately 416' L x 12' W x 1' H. Replace material that was washed away. Install 51cy of 1 ½ " surface gravel approximately 416' L x 10' W x 4".

Location Approximately 23 miles South of Havre.

****CB 11:** Install 60cy of 1 ½ " surface gravel approximately 340' L x 14' W x 2".

Location Approximately 23.2 miles South of Havre.

****Quarter Gulch:** Replace culvert 18" x 20' L and install 2cy of 1 ½ " surface gravel approximately 20' L x 15' W x 2".

Location Approximately 23 miles South of Havre.

****NC 14, 15:** Install 45cy of 1 ½ " surface gravel approximately.

Location Approximately 23.8 miles South of Havre.

SC 6: Install 14cy of 1 ½ " surface gravel.

Location Approximately 24.5 miles South of Havre.

****Blackie Coulee Road & Crossing:** Install Subbase 147cy of Aggregate Base Course approximately 1,320" L x 2' W x 1.5' D to fill rutting that exists. Install 391cy of ABC Material approximately 2,640' L x 12' W x 4" D. Install 293cy of crusher fine (road Surface Base) approximately 2,640' L x 12' W x 3" D. Install ten 16' x 5" x 12" T water bars made from 2 x 6 treated lumber and recycled conveyor belt material.

Location Approximately 24.3 miles South of Havre.

Publish: The Havre Weekly Chronicle

Legals November 26th, 2025

December 4th, 2025